

# CEDAR HOMES

PO Box 8265 • Fort Collins, CO • 80526  
Toll-Free: 800-98CEDAR • Phone: 970-267-0424 • Fax: 970-267-0498  
www.CedarTimbers.com

## Standard Materials

### Timber Package

- Laminated 5x8 Nominal Cedar Faced Exterior Wall & Gable End Timbers
- Interior 2x4 & 2x6 Framed Walls 16" OC Spacing
- Cedar Starter Strip
- 2x6 PT Mud sill
- TJI Main Level Floor Joists
- TJI Main Level Blocking
- TimberStrand Main Level Rim Joists
- 3/4" T&G Main Level Subfloor
- Glu-Lam Loft Beams (exposed)
- 2x6 SPF Loft Deck Boards (exposed, V-notched, T&G)
- 2x4 Loft Sleepers
- 3/4" Plywood Loft Subfloor/Underlayment
- Glu-Lam Posts (w/connective hardware)
- Prow Materials: (if prow design)
  - 2x6 framed walls 16" OC
  - 1/2" wall sheathing
  - 6x10 built-up headers
  - full height glu-lam prow post
  - 1x8 cedar siding (to match exterior of timbers)
  - 1x8 cedar paneling (to match interior of timbers)
- Framed Exterior Walls: (if any framed exterior walls in design)
  - 2x6 framed walls 16" OC
  - 1/2" wall sheathing
  - 6x10 built-up headers
  - 1x8 cedar siding (to match exterior of timbers)
  - 1x8 cedar paneling (to match interior of timbers)
- Glu-Lam Roof Beams (exposed)
- Purlin Wedges
- 2x6 SPF Loft Roof Boards (exposed, V-notched, T&G)
- 15lb. Building Felt (above 2x6 Roof Boards)
- 3-1/2" Rigid Insulation w/Furring (Approx. R-30)
- 1/2" Roof Sheathing
- 15lb. Building Felt (above Roof Sheathing)
- 30 Year Fiberglass Reinforced Shingles
- Roof/Wall Flashing
- 2x Rough Sawn Cedar Barge & Fascia Boards
- "Milgard" Brand Vinyl Windows, Insulating Glass, Screens
- "Milgard" Brand Sliding Glass Door (if any on plan), Insulating Glass, Screen
- 1x4 Rough Sawn Cedar Window Trim
- 6-Panel Fir, Exterior Grade Front Door (pre-hung, weather strip w/adj sill)
- 6-Panel Fir, Interior Doors (pre-hung)
- Stairs from Main Level to Loft Level: (if loft design)
  - 2x12 HF Stair Stringers
  - 5/4" PB Stair Treads
  - 1x8 Pine Stair Risers
- 2x6 Clear Pine Stair Railing
- 2x2 Clear Pine or Fir Stair Balusters
- 1x3 Nominal Clear Oak or Cedar Base Trim
- 1x3 Nominal Clear Oak or Cedar Window & Door Trim
- 1x2 Nominal Clear Oak or Cedar Beam Wrap Trim
- 1x8 Cedar Siding at Rim Joist
- Caulking for Exterior
- Adhesive for Floors
- 3-M Adhesive and "Oly-Log" Fasteners for Exterior Wall Timbers
- Shipping of Materials to jobsite (FOB)
- Plans (engineering, if any, not included)

All materials begin on main level – subject to change without notice  
2-25-2004